

CONDENSATE REMOVAL PUMP

The next generation Silent+ Mini Lime has an anti-vibration damper and built-in sound absorbing materials. As well as a guick release reservoir, you can also commission the pump on site, and check operation via the LED system in the reservoir. Silence isn't golden, it's lime.



12L/h max. flow



10m max. rec. head (flow rate 6L/h)



Max. flow

Max. rec. head

dB(A) @ 1m

Power supply

Max. unit output

Max. water temp

Discharge tube

IP Protection

Safety switch Thermal protection Self priming

Rated

Class

20dB(A) @ 1m




- Anti-vibration damper
- Pump sits in trunking elbow
- LEDs provide visual operating feedback

SUITABILITY



SILENT⁺ PUMPS

- Up to 16kW / 54,000Btu/h
- High wall split systems
- Left or right install with range of trunking systems
- ✓ Perfect for... Commercial use where silence is important





12L/h @ 0m head

10m

20*

230 VAC, 0.1A, 16W, 50/60Hz

Non continuous


16kW / 54,000Btu/h

40°C / 104°F

6mm ID

IP24 5.0A N.C. / N.O.**

II appliance 🔲



SILENT+ MINI LIME SYSTEM OPTIONS						
System		Co	lour	Part No.		
Option 1	★ 80mm →	0	lvory	FP3312/3		
"	50mm	0	White	FP3319/3		
Option 2	→ 70mm →	0	Ivory	FP3316/3		
ıı .	65mm	0	White	FP3320/3		
Option 3	62mm	0	Ivory	FP3317/3		
u .		0	White	FP3321/3		
Option 4	79mm	0	Ivory	FP3315/3		
"	60mm	0	White	FP3314/3		
Option 5 (EU only)	60mm	0	White	FP3327/3		
Silent+ M	FP3322/3					

† Pump only - no trunking included

SUGGESTED XTRA ACCESSORIES					
Description		Part No.			
1 Amp Fuse		FP2620			
Tube To Soil Stack Adaptor		FP2038			
Vinyl Tube Braided 1/4" (6mm)	**************************************	AX5100			
For more installation accessories take					

For more installation accessories take a look at our Aspen Xtra range

IN THE BOX

Silent⁺ Mini Lime pump (including 1.5m hard wired power cable) • Anti-vibration pulse damper, anti-siphon device • 500mm Lime green inlet hose 14mm ID • 40mm Vinyl breather tube 6mm ID • Elbow front and back • 800mm Conduit front and back • Internal

- conduit sleeve (Option 1 Slimline system only)
- Gasket (Option 1 Slimline, Option 2 and Option 3 Inoac systems only) • Ceiling plate
- Drain connector kit Fixing kit
- Install manual
- Download manual at aspenpumps.com View install video at aspenpumps.com

*Assuming solid wall construction with a 2kW unit ** 5.0A volt free with Normally Closed/Normally Open contacts. Default factory set to Normally Closed mode

Information correct at time of going to press